



COMPUTER CELL

(Information & Communication Technology)
University of Engineering and Technology, Lahore

CORRIGENDUM

With reference to the advertisement that appeared in the National Newspapers (Daily Dawn & Jang Lahore dated June 13, 2018) vide IPL-6337, PPRA & UET websites dated June 13, 2018 regarding expansion and up-gradation of IT Network of UET Lahore Main Campus, following changes have been made.

1. The bids opening date has been changed to **July 23, 2018 instead of July 02, 2018**.
2. Some changes in the technical specs and terms & conditions are listed in the table below:

Terms of Payment	<ol style="list-style-type: none">1) 30% payment upon delivery of passive equipment. (Not more than 75% of estimated cost of the delivered equipment).2) 20% payment upon delivery of Active equipment. (Not more than 75% of the estimated cost of the delivered equipment).3) 40% payment on project sign-off4) Remaining 10% payment will be held as performance security already mentioned in the RFP.5) A bank guarantee amounting to 10% of the project contract cost from scheduled bank will be provided by the successful bidder at the time of signing of contract. It will be returned on signing of provisional acceptance test (PAT).
Passive Equipment: UTP Cable	<ol style="list-style-type: none">1) UTP Cable should meet the standards (ISO/IEC 11801, ANSI/ TIA-568-c.22) All cables and connecting component should be UL listed (under writes Laboratories)3) Certificates should be submitted for the above clause4) Cat6 UTP cable must be DELTA Verified.5) CAT6 Cable should also be CM-R Certified for risks applications.6) Submission of product environmental profile(PEP)
UPS	<ol style="list-style-type: none">1) Input voltage: 110VAC to 280VAC instead of 110VAC to 300VAC for 1KVA and 2KVA UPS2) Should be American or European brand3) Input: L-N: 80-280V \pm 5 AC, 40Hz~70Hz for 10KVA UPS
Fiber Optical Cable deployment	Fiber deployment with Digging 9,000 meters
Data Cabinets (12U)	Data Cabinet - 12U Double Section with 2 Fans for switches with 8 Ports PDU and PDU should be verified by ROHS & CE
Power Supply requirements	Power cable 7/29 (Pure copper) = 20 Coils (10 Red + 10 Black) Light Plug 5 in 1 with back box = 70 Duct 16x25 = 10 feet length = 330 lengths
Bid Validity	Bid validity up to 90 days
Project Completion	Project should be completed in 150 Days instead of 120 Days
Evaluation Criteria S. No. 8 Page # 10	Company's equity as reported in the audited accounts should not be less than Rs. 100 Million

Prof. Dr. Waqar Mahmood
Director